WATER SUPPLY DIVISION.

Notification dated 17th August 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, up to 31st August 1929 till 3 P.M., for constructing a masonry Tank (12′ x 12′ x 6′) of 5,000 gallons capacity at Mavalli at the end of 1st cross road, Basavangudi, Bangalore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 31st October 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Water Supply Division, between the hours of 11 A.M. and 5 P.M., office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 85 only, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a masonry Tank (12′×12′×6′) of 5,000 gallons capacity at Mavalli at the end of 1st cross road, Basavangudi, Bangalore City," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Abstract estimate of quantities for constructing a Masonry Tank (12′×12′×6′) of 5,000 gallons capacity at Mavalli at the end of 1st cross road, Basavangudi, Bangalore City.

No.	Items of work	Per	Quantity
1	Earthwork excavation	Cyd.	38
2	Jelly concrete in surki mortar	C.ft.	951
3	Burnt brick in surki mortar	Do	1269
4	Cement plastering	Sqr.	4·56
5	Surki plastering	Do	4·86
6	Cement grouting and constructing a masonry bund at the corners inside the tank.	R.ft.	74
7	4″×7″ M. S. Girders including carting and hoisting ...	Cwt.	11
8	Jach arch terracing complete	Sqr.	2·25
9	Cornice alround	R.ft.	64
10	1½′×9″ parapet complete	Do	57
11	Manhole at the top complete with door, etc. ...	L. S.	Rs.
12	Iron ladder	R.ft.	8
13	Burnt stone slabs 4″ set in mortar	S.ft.	23
14	Inserting over flow drain pipes with pipe each ...	L. S.	Rs.
15	Cement concrete	C.ft.	72
16	Rain water pipe and colour washing	L. S.	Rs.
	LABOUR.		
1	Earthwork excavation 490 x 3 x 2=2,940 c.ft. ...	Cyd.	109
2	Laying and jointing 3″ pipes	Cwt.	63
3	Removing and relaying pipes 3″ and 2½″	Do	3
4	Lead joints 3″	No.	40
5	Lead joints 2½″	,,	4
6	3″ cast iron cuts	,,	12
7	2½ do	,,	4
8	3″ cement joints	,,	40
9	Fixing branches and valves	,,	11
10	Constructing cisterns for valves	,,	4
11	3″ wall bores and redoing	,,	2
12	Carting 3″ cast iron pipes from the Railway Station to work spot (Mavalli) 4 miles including loading and unloading from carts and unloading from wagon.	Cwt.	63

B. R. GARUDACHAR,